

LIBER 1 PG 1105  
 STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 94 MAR 15 PM 1 37  
 Clerk-Register  
 Register of Deeds Stamp & File Number

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Kalamazoo  
 (County)

Located In:	Corner Code #
T 2 S R 10 W	I-4
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- Comstock Section 10  
 1. Public Land Survey  
 2. Property Controlling in Section  
 3. Miscellaneous Property in Sec.  
 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on February 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 Original corner established by U.S. Government Survey in 1825-Set Post.  
 Wh. Oak 12" North 32°-E 10 Lks (6.6')  
 Wh. Oak 10" South 25°-W 5 Lks (3.3')  
 1872-F. Hodgeman County Surveyor-found stake from stump of one witness. Plated new stake  
 Wh. Oak 12" South 11½°-W 31 Lks (20.46')  
 Wh. Oak 16" North 82°-E 16½ Lks (10.89')  
 1885-F. Hodgeman County Surveyor-found stake corrected by bearing trees of resurvey standing. Set Post.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 3" round tile with "X" on top from 1959 Witness-6" Deep, steel "T" Fence Post on North side of tile. A survey iron is 165'-East of tile.  
 9" Hickory North 82°-W 2.6'-Gone  
 20" Oak South 12°-E 61.35'-Gone  
 13" Oak East 27.2'  
 18" Oak North 20°-W 32.7'-Gone  
 Twin 20" Oak South 06°-W 36.9'-Gone

*RES*  
 RATIFIED  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP  
 3-3-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I-4 East 1/4 Post of Section 10, T. 2 S., R. 10 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 3, 1994. Found 3" round tile as called for in 1885 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Placed remonumentation sleeve over tile.

- PK Nail in S side 24" Oak North 60°-W 25.18'
- PK Nail in E side 12" Oak South 10°-W 36.15'
- PK Nail in N side 18" Oak South 75°-E 27.66'
- PK Nail in S side 15' Oak South 60°-E 28.65'

Signed by Robert E. Snell  
 Surveyor's Michigan License No. 9734

Date 3/15/94  
*R.E.S.*