

**SURVEY & REMONUMENTATION**

FEB 26 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 272

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
97 DEC 23 PM 12 57  
CLERK - REGISTER

For corners in SECTION

Kalamazoo	Located In:	Corner Code#
(County)		
Comstock Township		
1. Public Land Survey	T 2S R 10W	I-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Gary D. Hahn, in a field survey on May 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 - East quarter post established by U. S. Deputy Surveyor Robert Clark, Jr.  
Witness ties: BR. Oak 14" S 1/2 deg. E 191 lks.  
BR. Oak 16" N 5 1/2 deg. W 219 lks.
- 1885 - F. Hodgman - "Set post with strap iron beside it. No tree near"  
Date ? - KCRC witness tie notes:  
(W) Found tile  
(W) R.R. rail N 2 deg. W 0.5 feet  
(W) In fence line north and south, east and west fence line N 0.5 feet  
(W) 10" Elm S 35 deg. W 72.7 feet  
(W) 24" W.C. in east fence 139.0 feet

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
6/19/97  
R. Hahn

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found tile 0.15 feet East and 0.20 North of post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-6, East Quarter post section 15, Town 2 South, Range 10 West, ratified by Kalamazoo County Remonumentation Peer Group on June 19, 1997. Position of tile is accepted as a careful and faithful perpetuation of the position of the original corner. Set steel sleeve over tile.  
Witness ties: R.R. rail fence post North 0.35 feet  
Set PK nail in East face 20" Cherry North 2.65 feet  
Set PK nail in West face 12" Cherry N 10 deg. W 19.29 feet  
Set PK nail in SW face 21" Pine S 40 deg. E 96.56 feet



Signed by [Signature]  
Surveyor's Michigan License No. 38116

Date 12/22/97