

**SURVEY &
REMONUMENTATION**

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'94 JAN 4 AM 9 02

For corners in **COMMISSION**

For corners in	<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #
	<u>Comstock Twp.</u>		
1. Public Land Survey	T <u>23</u> R <u>10W</u>		<u>P-12</u>
	T ___ R ___		_____
	T ___ R ___		_____
	T ___ R ___		_____
2. Property Controlling in Section	S ___ T ___ R ___		_____
	S ___ T ___ R ___		_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		_____
	S ___ T ___ R ___		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

James E. Baynton
CLERK-REGISTER

LIBER **1** PG **1051**

Register of Deeds Stamp & File Number

I, James E. Baynton, in a field survey on Dec. 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Quarter post established by U.S. Government Deputy Surveyor John Mullet in 1827. Remonumentation by F. Hodgeman in 1885. Set standard tile, witness: Bearing tree standing. Tile found and witnesses taken: 0.5' East of fence corner; 24" W.O. N.10°E, 41.0'; 24" Birch N.15°W, 106.0'; 18" W.O. S.45°E, 44.0'; 8" Iron-wood S.68°W, 18.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile from witnesses.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-30-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found tile accepted as careful and faithful perpetuation of the original corner. Set standard remonumentation sleeve over tile, new witnesses: 0.5' west of fence corner; 0.81' South of fence; 10" Maple west 3.15' to nail; fence post S.20°W, 21.46' to nail; 15" Maple S.25°E, 18.41' to nail.

Signed by James E. Baynton Date Dec. 29, 1993
 Surveyor's Michigan License No. 29239