

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PG 1090

For corners in

Kalamazoo
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-------------|------------|
| 1. Public Land Survey | T | <u>2 S</u> | R | <u>10 W</u> | <u>J-5</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
94 JAN 21 AM 8 56
Register of Deeds Stamp & Fee Number

LIBER 1 PG 1090
CLERK - REGISTER
Jessie B. Stump

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5					*								
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826-United States Government Survey-Set Poast

- W. Oak 24" North 56°-E-22 Lk (14.52')
- W. Oak 16" South 41°-W-33 Lk (21.78')

1872-F. Hodgeman-Original Corner lost. Bisected line between Southeast and Southwest Corner

- Planted stake and brick
- Cherry - 10" North 30 1/4 E-84 1/2 Lks (55.77')
- W. Oak - 6" South 61°-E-62 1/2 Lks (41.25')

1885-F. Hodgeman-Found stake and brick-bearing trees still standing. Set Earthen Post with

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Earthen and brick under Found tile from previous surveys in monument box over corner

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**
12/16/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 South 1/4 Post Section 11, T. 2 S., R. 10 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on December 16, 1993. Found solid clay tile as called for by 1885 Remonumentation by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner position. Placed remonumentation sleeve over tile.

- PK Nail in Southeast Side P.P. South 55°-W 54.41'
- PK Nail in Southwest Side P.P. South 70°-E 38.92'
- PK Nail in Northwest Side 14" Hickory North 70°-E 40.9'
- PK Nail in Northeast Side P.P. North 41°-W 85.20'

Signed by

Robert E. Snell

Date

1-20-94

Surveyor's Michigan License No. 9734