

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PG 1110
 '94 MAR 15 PM 1 37
 STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 Register of Deeds Stamp & File Number

For corners in

Kalamazoo
(County)

Located In:

Corner Code #

1. Comstock Section 24
 Public Land Survey

T 2 S R 10 W K-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

2. Property Controlling
 in Section
 3. Miscellaneous
 Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on February 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1827-U.S. Government Survey-Set Post.
 Wh. Oak 14" North 43°-E 42 Lks (27.72')
 Wh. Oak 18" South 35½°-W 70 Lks (46.20')
 1886-F. Hodgeman County Surveyor-found stone and stake under at point 5.00 North of South end Hedge and 12.32 Ch. from the river. Stump of bearing tree Southwest taken out and lying on the ground. Set Post. No tree near.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 3" round clay tile with "X" on top 10"± below surface with three R.R. Spikes along side of tile.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 3-3-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-8 West 1/4 Post Section 24, T. 2 S., R. 10 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 3, 1994. Found 3" round clay tile with "X" on top as called for in 1885 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Placed remonumentation sleeve over tile and placed R.R. Spikes along side and a ½" x 12" Iron over.

SE Cor. Conc. Foundation Apartment Bldg. North 40°-E 66.26'
 SW Cor. Conc. Foundation Apartment Bldg. North 42°-W 71.37'
 SE Cor. Conc. Foundation Garage Bldg. North 74°-W 79.98'
 Sanitary Manhole Cover South 14°-W 18.58'

Signed by Robert E. Snell Date 3-15-94
 Surveyor's Michigan License No. 9734