

SURVEY &  
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

94 JAN 4 AM 9 02

For corners in

Kalamazoo  
(County)

Comstock Twp.

Located In:

Corner Code #

T Z S R 10 W

K-9

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

1. Public Land Survey

2. Property Controlling  
in Section

S \_\_\_\_\_

S \_\_\_\_\_

S \_\_\_\_\_

S \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*James E. Boynton*  
CLERK-REGISTER

LIBER 1 PG 1055

Register of Deeds Stamp & File Number

I, James E. Boynton, in a field survey on Dec. 27, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Quarter post set by U.S. Government Deputy Surveyor John Mullet in 1827. Remonumentation by F. Hodgeman in 1885. Set standard tile, witnesses; W.O. N.40°E. 125 1/2'; Hick. 4 S.04W 89.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile in monument box from witnesses; 16" Sassafras - <sup>63</sup> 58'; 16" Sassafras S.01°W 16.29'; 30" Oak N.40°E. 83.22'; 14.90' <sup>South</sup> ~~North~~ of centerline of Miller Road.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
12-30-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found tile accepted as careful and faithful perpetuation of the original corner location. Set standard remonumentation stone over tile, new witnesses: tile is 15' South of centerline of Miller Road; P.P. S.10°W. 46.38' to nail; Twin 14" Elm S.75°W. 78.26' to nail; 6" Locust N.20°W. 41.81' to nail; 30" Oak S.45°E. 83.06' to nail; at house #9988.

Signed by James E. Boynton

Date Dec. 29, 1993

Surveyor's Michigan License No. 29239