

**SURVEY &
REMONUMENTATION**

JUL 23 1997

LIBER 2 PAGE 127

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Comstock Twp.

Kalamazoo Located in: Corner Code # -
(County)

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>2S</u> R <u>10W</u> | <u>L-06</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 APR 25 AM 10 26
Annexed
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on April 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

This corner not set by Original Government Surveyors.

1934: Glen Wheaton, County Surveyor: Set monument at Northeast corner Lot 133 in Assessor's Plat of City of Galesburg, recorded in Liber 13, Pages 18-22 of Plats, March 6, 1934. (Also shown as center 1/4 post Section 13).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" iron pipe in 3" square concrete.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**
4-17-97 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-06: Center 1/4 post Section 13, T. 2 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 17, 1997 and is accepted as the best available evidence of the position of the corner. This corner not set by Original Government Surveyors. Found 3" x 4' concrete monument as set by Glen C. Wheaton in Assessor's Plat of City of Galesburg, recorded March 3, 1934 in Liber 13 of Plats, Pages 18-22.

Monument is in tree line to West

Center of Tree line to South

Exist. Nail/Tab in South Side

Exist. Nail/Tab in West Side

Exist. Nail/Tab in South Side

18" Twin W. Cherry

15" Hickory

6" Hickory

West 4.0'

S. 86° E. 34.54'

S. 14° W. 14.47'

S. 85° W. 24.48'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date 4-21-97