

SURVEY &  
REMONUMENTATION

FEB 18 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
94 JUN 21 AM 8 56  
*James P. [Signature]*  
CLERK - REGISTER

For corners in

Kalamazoo

(County)

Located in:

Corner Code #

- |                                    |   |            |   |             |            |
|------------------------------------|---|------------|---|-------------|------------|
| 1. Public Land Survey              | T | <u>2 S</u> | R | <u>10 W</u> | <u>L-9</u> |
|                                    | T |            | R |             |            |
|                                    | T |            | R |             |            |
|                                    | T |            | R |             |            |
| 2. Property Controlling in Section | S |            | T | R           |            |
|                                    | S |            | T | R           |            |
| 3. Miscellaneous Property in Sec.  | S |            | T | R           |            |
|                                    | S |            | T | R           |            |

LIBER

1 PG 1091

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on December 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1825-Original Government Survey Set Post  
Beech 12" North 88°-E-41 Lk (27.06) Gone  
Sugar 8" South 33°-E-12 Lk (7.92) Gone

- 1885-F. Hodgeman County Surveyor  
Found Stone of Re-survey  
Set Earthen Poast  
Whitewood 18" South 56°-W-86½ Lk (57.09) Gone

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner with original accessories not found  
December 29, 1993 Found Tile (Earthen Post) set by Hodgeman

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
*12/30/93*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 South 1/4 Post Section 24, T. 2 S., R. 10 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on December 30, 1993. Found tile as called for by 1885 re-survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Placed monument sleeve over tile.

- |                        |                |             |        |                     |
|------------------------|----------------|-------------|--------|---------------------|
| Nail in North Side     | 12" Sassafras  | North 60°-W | 13.85' | South Row Fence for |
| Nail in Northwest Root | 20" Double Ash | North 40°-E | 5.27'  | I-94 North 47.5'    |
| Nail in                | 10" Hickory    | East        | 10.77' |                     |
| PK Nail in             | 6" Oak         | South 25°-W | 21.95' |                     |

Signed by

*Robert E. Snell*

Date

*1-20-94*

Surveyor's Michigan License No.

9734