

APR 01 1996

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'95 DEC 8 AM 10 55

For corners in KALAMAZOO Located In: _____ Corner Code # _____
(County)

KALAMAZOO TWP.

1. Public Land Survey	T	<u>2S</u>	R	<u>11W</u>	<u>A3</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

James Young
CLERK-REGISTER

LIBER **1 1397**

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Gary D. Hahn, in a field survey on July 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 Corner post established by U.S. Deputy Surveyor Grange Risdon. "Int. W. boundary 168 lks. South of post. Set post cor. to sec. 6 & 7." Aspen 16in N43°E 41k Aspen 15in S34°E 451k
- 1864 Stimson "Planted stake" "Point in line between line between sec. 6 & 7 but not certain to be on the range line."
- 1869 F. Hodgman "sec. cor. set by F. Stimson p.37 not verified, doubtful about being on the sec. line."
- 1870 F. Hodgman "sec. cor. set 1.68 ch. South of the corner sec. 1 & 12 - planted stake stone & brick & marked."
- 1905 E. Strong "Found tile at NW. cor. 5 1/2 lks. N. of old fence line and at correct distance south of the Oshtemo companion corner of brick. Said brick comes to the surface and is worn and needs iron."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered.

Found 12 inches of tile standing erect 1/2 foot beneath road sub base. Removed tile and dug underneath. Found no more evidence.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-21-95
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A3, Northwest corner Section 7, T2S, R11W, Ratified by Kalamazoo County Remonumentation Peer Group on Sept. 21, 1995. Tile is accepted as a careful and faithful perpetuation of the position of the original closing corner. Removed tile (not deep enough to set monument on top of and too deep for sleeve) and set a 30" Harrison monument in monument box

- Set P.K. nail in 16" Walnut East 39.54'
- Set P.K. nail in 4" Maple S70°E 63.51'
- Set P.K. nail in 26" Hickory S40°W 39.22'
- Set P.K. nail in 8" Ash N80°W 29.31'



Signed by *[Signature]*
Surveyor's Michigan License No. 38116

Date November 17, 1995