

**SURVEY &  
REMONUMENTATION**

APR 27 1995

**COMMISSION**

LIBER

1 PG 1197

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Kalamazoo

(County)

Located In:

Corner Code #

Kalamazoo Township

T 2 S R 11 W

B-4

1. Public Land Survey

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on May 4, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1874: E. Strong, County Surveyor; Large stone at intersection of 1/4 Lines.

Br. Oak 20" South 06 1/4° West 46 Lks

1935: Wilkins & Wheaton Engineering; Found stone. Side stone 33.35' South.

Cherry 12" South 05° East 27.9'  
Telephone Pole Southwest 66.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found PK Nail on split between plat monuments (West line of Grand Prairie Village and Skyline Plats). Original stone removed during sewer construction in 1981.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 Center of Section 7, T. 2 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found PK Nail mid-way between plat monuments (see "B" above). This position not established by original government surveyors. This monument is accepted as best available evidence of the position of the corner. Placed 20" Harrison monument and placed monument box over.

CL	Hydrant	South	25.18'	
Plat Monument	(1/2" iron in concrete)	North	32.89'	CL Grand Prairie Rd
Existing Nail/Tab	in Southerly Side Power Pole	N 72° W	65.30'	South 1.0'
Existing Nail/Tab	in Southerly Side Power Pole	S 70° W	68.45'	

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
94 DEC 9 AM 9 24  
CLERK - REGISTER

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
7-21-94

Signed by

*Robert E. Snell*

Date

12-9-94

Surveyor's Michigan License No.

9734