

SURVEY & REMONUMENTATION

AUG 06 1996

2 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo
(County)
Kalamazoo Twp.

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|------|---|-------|------|
| 1. Public Land Survey | T | 2 S. | R | 11 W. | B-07 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |

CLERK - REGISTER
James P. [Signature]

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
96 MAY 23 PM 1 47

LIBER 1 PAGE 1494
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on February 19, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827: United States Government Surveyors; set 1/4 Section post.
Br. Oak 12" S. 43 $\frac{1}{2}$ ⁰ E. 541 lks.
Br. Oak 6" S. 89⁰ E. 128 lks.

1885: F. Hodgman, County Surveyor; found stake hole at intersection of fences, set post. No trees near.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1954: Wilkins & Wheaton Engr. Co.; found tile.

3" Cherry N. 59⁰ E. 36.8'
10" Cherry S. 07 $\frac{1}{2}$ ⁰ E. 78.4'

1996: Found 3" round tile with "x" on top from 1954 witnesses.

East & West Wire Fence North 9.0'
North & South Wire Fence East 2.5'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-07: South 1/4 post Section 18, T. 2 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on March 21, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top as placed by F. Hodgman, County Surveyor in a remonumentation survey in 1885. Placed remonumentation sleeve over tile.

PK Nail in East Side	7" W. Cherry	S. 03 ⁰ W.	29.92'
PK Nail in North Side	28" W. Cherry	N. 40 ⁰ W.	18.23'
PK Nail in South Side	15" W. Cherry	N. 22 ⁰ E.	18.76'
PK Nail in South Side	R.R. tie fence corner	N. 75 ⁰ E.	2.30'

R.E.S.
RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3-21-1996

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 5-23-96

