

SURVEY & REMONUMENTATION

FEB 26 1998

LIBER PAGE 256

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 DEC 22 AM 8 59
Clerk - Register
Annexed

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Kalamazoo Township		
1. Public Land Survey	T 2 S R 11 W	C-1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William K. Crane, in a field survey on May 29, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1		●										
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1827, John Mullett, DS:

- 7" Beech S 73° E 42 links
- 30" Beech S 57° E 27 links

County Surveyor Records, Volume 1, Page 382, Hodgman, 1882:

- Found stake hole from US depression
- 12" Maple N 59° W 90 links
- 10" Maple S 3½° E 7½ links

Volume 6, Page 485, Hodgman:

- 6" Maple N 43½° E 67 links
- 20" Beech S 6½° E 53 links

LCRC, Liber 1, Page 965, Thomas Chettleburgh:

- Iron bar in monument box
- PK N side P. Pole S 78° W 65.62'
- Nail NE side P. Pole N 49° W 101.88'
- C/L Hydrant N 21° W 62.20'
- Nail SE side P. Pole N 42° E 28.18'
- Nail SE side 39" Maple N 58° E 45.68'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-19-1997
[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Removed 5/8" iron and monument box, dug 2' ± and found clay tile with "X". Set Harrison monument over top of clay tile and reset monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is accepted as a careful and faithful perpetuation of the position of the original corner. Set Harrison monument over clay tile and reset monument box.

- Found PK nail N side U. Pole S 78° W 65.49'
- Found nail NE side U. Pole N 49° W 101.90'
- Found nail SE side U. Pole N 42° E 28.31'
- Found nail SE side 39" Maple N 58° E 45.78'
- Top of center of Fire Hydrant N 21° W 62.23'

Signed by *William K. Crane*
William K. Crane, P.S.

Date December 22, 1997

Surveyor's Michigan License No. 29243