

SURVEY & REMONUMENTATION

AUG 06 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 026

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code #	
<u>Kalamazoo Township</u>			
1. Public Land Survey	T <u>2S</u> R <u>11W</u>	<u>C-13</u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
4. Lot No. _____	Recorded Plat _____		
5. Private Claims _____			

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
JUN 7 PM 2 26
1996
Clerk - Register
Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on Feb. 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; set post common to Sections 31 and 32.
 Wh. Oak 8" N. 21 $\frac{1}{2}$ ⁰ E. 241 lks.
 Wh. Oak 10" N. 79⁰ W. 320 lks.

1885: F. Hodgman, County Surveyor; found stake with stone over it 20 lks. West of angle of fence and stone at the corner of Section 5 and 6, T. 3 S., R. 11 W. Set post with stone over it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1955: Hill 'N' Brook Village No. 5, recorded in Liber 21 of Plats on Page 22. Calls for State of Michigan Brass Cap and plat monument at the Northwest corner of Section 5, T. 3 S., R. 11 W.

1996: Found 4" round concrete monument with State of Michigan Brass Cap on top which reads, Southwest corner Section 32. Found plat monument 13.23' East, at Northwest corner Section 5, T. 3 S., R. 11 W.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5-2-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13: Southwest corner Section 32, T. 2 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 2, 1996, and is accepted as the best available evidence and perpetuation of the corner. Left 4" monument with State of Michigan Brass Cap, in top as remonumentation monument.

- Plat Monument S. 80⁰ E. 13.23'
- PK Nail on East Side of 26" Oak
- PK Nail on Southwest Side of 22" Twin Wild Cherry
- PK Nail on South Side of 12" Wild Cherry
- PK Nail on Southeast Side of 28" Oak

- S. 14⁰ W. 7.63'
- N. 48⁰ W. 19.09'
- N. 86⁰ E. 10.72'
- S. 40⁰ E. 15.23'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 6-6-96