

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo Twp.

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 29 AM 11 26
Clerk - Register

Register of Deeds Stamp & File Number

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T 2S R 11W	D-03
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on July 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 8-20-1998

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3				●									
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1827: United States Government Surveyors; set 1/4 Section post.

W. Ash 14" S. 16° E. 18 lks.
Beech 7" N. 41° W. 18 lks.

1884: F. Hodgman, County Surveyor; "Found stake, stone, and brick N. 22° E. 46 lks. from witness of resurvey. Bored 3', put 1 ft. brick in bottom and 2' earthen post over with stones around."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1949: Wilkins & Wheaton Engr. Co.; found tile, Elm 18" N. 65° E. 62.0', Elm N. 01° W. 29.3', Elm 5" S. 45° E. 31.15', W. Cherry 12" N. 50° W. 33.0'.

1960: Michigan State Highway Department, J. Corbit; 1/2" steel rod, 23" Elm N. 10° W. 29.32', 6" Cherry S. 30° W. 27.33', 20" Cherry N. 60° W. 34.45'.

1985: Wilkins & Wheaton Engr. Co.; 1" pipe in monument box, bridge abutment S. 30° W. 19.80' (outside face). Bridge abutment N. 75° W. 58.35', light pole w/cut nail N. 15° E. 25.29'.

1998: Found 1" iron pipe in monument box in traveled center line of Barney Rd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-03: South 1/4 post, Section 5, T. 2 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on August 20, 1998 and is accepted as the best available evidence of the position of the original corner. Found 1" iron pipe in monument box in overpass Business Route U.S. 131. Placed 30" Harrison monument in monument box after reconstruction of bridge deck.

Notch in North Edge Guard Rail "I" Beam	N. 35° E.	22.08'
Notch on Top of Curb over Inlet (12" CMP)	S. 38° E.	29.21'
Notch on Top of Concrete Guard Rail	S. 30° W.	19.80'
Notch on Top of Concrete Curb (flow way)	N. 40° W.	29.83'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-29-98