

SURVEY & REMONUMENTATION

JUL 23 1997

LIBER 2 PAGE 115

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T	<u>2S.</u>	R	<u>11W.</u>	D-5
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 97 MAR 20 PM 3 35
 J. J. [Signature]
 CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on January 9, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - Orange Risdon, D.S., Set quarter Section post, W. Oak 30" S. 66° W. 10 lks., Cherry 10" N. 60° E. 84 lks.
1866 - F. Stimson, C.S., Planted stake and several stones and a brick in hole dug around stake. Tree standing S.W.

1884 - F. Hodgman, C.S., Found stone and brick N. 66° E. 10 lks from stump of bearing tree. Set post with brick under and stone around. Y. Oak 24" about North 107½ lks., Elm 16" N. about 85° W. 25lks.

1992 - Curtis Newhouse, R.L.S., Records L.C.R.C. L. 1, Pg. 949 "Found 3" clay tile with "X". North 0.3' 1" pinched pipe. North 49.4' S.W. cor. of garage at 2407 Hillsdale Ave.. N. 80° E. 43.5' S.E. cor. of house at 2407 Hillsdale Ave., South 13' 12" Oak. N. 45° W. 42.7' 15" Twin Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile 0.5' below grade per 1992 witnesses, said tile was surrounded with stones.

R. J. [Signature]
RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
 2-27-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed standard sleeve tile, Accessories:

- 60d nail in Twin 12" Oak S. 60° W. 21.30'
- 60d nail in 12" Oak S. 25° E. 12.90'
- Most Southerly corner of House #2407 N. 65° E. 43.70'
- Most Westerly corner of House #2407 N. 10° W. 49.56'



Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 3/18/97