

APR 01 1996

COMMISSION

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

95 NOV 16 PM 3 26

For corners in City of Kalamazoo  
Kalamazoo  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 2S. R 11W. D-7
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*James [Signature]*

CLERK-REGISTER

LIBER 1 1371

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_
- 6. 104M Job # 25826

I, Allen H. McMachen, in a field survey on May 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7		●										
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1825 - J. Mullet, D.S. Set 1/4 Section post  
Br. Oak 10" S. 65° W. 25 lks.  
Br. Oak 10" N. 71° E. 92 lks.
- 1906 - Ed Strong, C.S. Found tile  
Br. Oak 20" S. 19 lks.

1864 - F. Stimson, C.S.  
Government corner lost and re-established by myself this dated by bisecting Section line "A"- "C" planted Burr Oak stake and stones and broken earthen from which a Burr Oak 10" N. 69 1/2° W. 62 lks., Wh. Oak 5" N. 38 1/2° E. 27 1/2 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile in Monument Box

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
6-15-95

*RES*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful re-establishment of the position of the original corner. Placed standard sleeve over found Clay Tile, Accessories:

- Nail & Tab in 30" Oak N. 85° W. 55.51'
- Nail & Tab in 6" Hickory N. 80° W. 43.20'
- Nail & Tab in 12" Hickory N. 40° W. 17.95'
- Nail & Tab in 24" Oak N. 05° W. 10.31'



Signed by Allen H. McMachen

Date 11/10/95

Surveyor's Michigan License No. 16935