

SURVEY & REMONUMENTATION

1
2

APR 27 1995

COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

91 DEC 15 PM 1 36

For corners in KALAMAZOO TWP.

<u>KALAMAZOO</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>11W</u>	<u>E-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. Jones
CLERK-REGISTER

LIBER 1 PG 1214

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Allen H. McMachen a field survey on March 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1880's - F. Hodgeman placed Clay Tile post during official Township Remonumentation.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile in East and West fence.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3/17/94

R. H. G.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as careful and faithful perpetuation of the original corner, placed Standard Sleeve over existing Clay Tile, accessories:

- Nail & Tab in North face of 12" Elm EAST 11.12'
- Nail & Tab in West face of 6" Cherry S. 25 deg. E. 37.48'
- Nail & Tab in North face of 10" Db1. Cherry S. 50 deg. W. 53.31'
- Nail & Tab in North face of 12" Elm WEST 8.97'

Signed by Allen H. McMachen Date 4/5/94
Surveyor's Michigan License No. 16935