

SURVEY & REMONUMENTATION

AUG 06 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

LIBER

2 PAGE 027

Kalamazoo

Located in:

Corner Code #

Kalamazoo (County) Twp.

1. Public Land Survey	T <u>2S</u> R <u>11W</u>	<u>E-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

95 JUN 7 PM 2 26

Jessica J. Stump
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Feb. 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827: United States Government Surveyors; set post common to Sections 28, 29, 32 and 33.
 Y. Oak 15" S. 01° E. 55 lks.
 W. Oak 12" N. 46° W. 321 lks.
- 1885: F. Hodgman, County Surveyor; found old stake at intersection of fence lines. Set post.
 Red Oak 2" North 2 lks.
 Hedge East 5 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1948: Wilkins & Wheaton Engineering Co.; found 4" concrete monument with State of Michigan Brass Cap on top.
 1996: Found 4" concrete monument with State of Michigan Brass Cap on top.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5-2-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11: Northwest corner of Section 33, T. 2 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 2, 1996, and is accepted as a careful and faithful re-establishment of the position of the original corner. Found 4" concrete monument with State of Michigan Brass Cap on top as shown in a survey by Wilkins & Wheaton Engineering Co. dated November 5, 1948, left 4" monument with State of Michigan Brass cap in top as remonumentation monument.

- | | | |
|--|-----------|--------|
| PK Nail on Northwest side in root of 20" Oak | S. 30° W. | 3.36' |
| Nail and Tab on West Side of 40" Oak | N. 34° E. | 35.38' |
| Northwest Face of Fence Post | S. 20° E. | 1.10' |
| Northeast corner of Metal Base to Parking Lot Light Base | N. 88° W. | 60.46' |

Signed by *Robert E. Snell*
 Surveyor's Michigan License No. 9734

Date 6-6-96