

1
2
SURVEY &
REMONUMENTATION
APR 27 1995
COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
DEC 15 PM 1 36

For corners in KALAMAZOO TWP.

KALAMAZOO Located In: Corner Code #
(County)

1. Public Land Survey T 2 S R 11 W F-2
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

James J. [Signature]
CLERK-REGISTER

LIBER 1 PG. 1224

Register of Deeds Stamp & File Number

I, Allen H. McMachen a field survey on March 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Pre 1929 - No available records were found.
1929 - County Surveyor found Stone.
Found Iron 728.70 North and center line of existing road 652.2' West.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" Iron rod 24" long 0.25' West of 3" dia. (O.D.) 5' high steel fence post (construction of fence is believed to have removed Stone). Found pinched pipe North Rec. 728.70', meas. 728.22'. Center line of road to West Rec. 652.2', meas. 651.48'. Line between Tile @ West 1/4 cor. and Iron @ East 1/4 cor. is 9.92' South of found Iron at center.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
This position not established by original Government Surveyors.
Found Iron rod is accepted as the best available evidence of the position of the corner. Removed Iron rod and placed Harrison monument.
Accessories:

- Nail & Tab in E. side 12" Maple N. 35° E. 16.73'
- Nail & Tab in N. side 10" Maple S. 55° E. 7.02'
- Nail & Tab in N. side 6" Maple S. 80° E. 28.45'
- Nail & Tab in S. Side 8" Double Hackberry EAST 63.07'

Signed by Allen H. McMachen Date 12/15/94
Surveyor's Michigan License No. 16935

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5			4		3		2		1		
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

