

SURVEY & REMONUMENTATION

AUG 06 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo
(County)
Kalamazoo Twp.

Located in:

Corner Code #

1. Public Land Survey

T 2S R 11W F-11

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

CLERK - REGISTER

Jessica J. [Signature]

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
95 JUN 7 PM 2 26

LIBER 2PAGE 028

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on Feb. 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1827: United States Government Surveyors; set 1/4 Section post.

Wh. Oak 6" N. 78° E. 103 lks.
Wh. Oak 12" S. 80° W. 111 lks.

1885: F. Hodgman, County Surveyor; found stake standing beside fence with stone and brick around. Set post with stone and brick around.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

1945: Wilkins & Wheaton Engineering Co.; found tile in a survey dated November 15, 1945.

1996: Retraced November 15, 1945 survey and found 4" concrete monument with State of Michigan Brass Cap in top in place of tile. Brass Cap is beneath large granite stone set in concrete. Notched out Northeast part of stone to verify location of Brass Cap.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5-2-1996 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

F-11: South 1/4 post of Section 28, T. 2 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 2, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found State of Michigan Brass Cap in place of 3" round tile as set by F. Hodgman, County Surveyor in 1885 remonumentation survey. Left 4" monument with State of Michigan Brass Cap in top as remonumentation monument.

Nail and Tab on West Side of 24" Oak
Nail and Tab on North Side of Triple 15" Oak
PK Nail on South Side of 7" Maple
PK Nail on North Side of 8" Maple

N. 30° E. 6.00'
S. 38° E. 5.03'
N. 56° W. 21.15'
N. 25° W. 46.57'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date 6-6-96