

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE LIBER  
Filing Requirement of Act 74, Mich. P.A. 1970

2 PAGE 373

For corners in Kalamazoo Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T 2S R 11W	G-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
1998 NOV 23 PM 2 57  
Clerk - Register  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on Aug. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1827: United States Government Surveyors; set 1/4 Section post.

White Oak 7" N. 36° W. 50 lks.  
White Oak 10" S. 10° E. 134 lks.

1885: F. Hodgman, County Surveyor; "found stone with tin wash basin over it, in line with board fences east and west and 50 lks. from road fence east. The stone is 1 1/2' long and 1 1/2' below the surface of the road. Put a 1 foot earthen post on top of stone and marked White Oak 16" S. 86 1/2° E. 81 1/2 lks., Yellow Oak 18" S. 40 1/2° E. 82 1/2 lks."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1949: Wilkins & Wheaton Engr. Co.; placed notch in concrete pavement, concrete monument West 33.00' on East & West 1/4 line of Section 33, iron 40' East in extension of East & West 1/4 line of Section 33. Red Oak 7" S. 87° W. 27.04', White Oak 8" S. 87 1/4° E. 52.8', Hickory 3" N. 40° W. 47.52', Yellow Oak 18" S. 40° E. 54.45'.

1998: During reconstruction of S. Westnedge Ave. found 1/2" iron in concrete. Returned later and found 1 foot section of 3" round tile on top of a large stone, 3 feet below surface of the road. Surface iron was 0.22' North of tile.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP 8-20-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12: East 1/4 post, Section 33, T. 2 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on August 20, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 1 foot section of 3" round tile on top of large stone. Tile was placed in 1885 Remonumentation survey by F. Hodgman, County Surveyor. Placed 20" Harrison monument over tile in monument box after base courses of pavement were in place.

1/2" Iron with Red Cap at back of curb at drive N. 60° W. 36.34'  
1/2" Iron with Red Cap at back of curb at drive S. 50° W. 54.40'  
PK Nail in South Side Power Pole S. 22° E. 42.01'  
1/2" Iron in Concrete Plat Monument S. 85° E. 44.02'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 11-20-98