

FEB 08 1999

1
2

SECTION

LIBER 2 PAGE 396

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T 2S R 11W	G-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 9 15
J. J. [Signature]
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Sept. 24 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; set post, corner to Sections 33 & 34.

Br. Oak 6" N. 29 $\frac{1}{2}$ ⁰ W. 84 lks.
 Br. Oak 8" N. 44⁰ E. 30 lks.

1885: F. Hodgman, County Surveyor; "Found rotten stake S. 29 $\frac{1}{2}$ ⁰ E. 84 lks. from U.S. Bearing Tree. Put in 3 foot post with stone around and marked Wh. Oak 24" S. 59⁰ W. 61 lks."

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1932: Wilkins & Wheaton Engr. Co.; Portage corner West 25.08'
- 1949: Wilkins & Wheaton Engr. Co.; Found tile 25.13' East of Portage corner.
- 1961: City of Kalamazoo; loss of tile during sewer construction. P.P. 50.64' NW, P.P. 24.28' SW. (no other bearings), Portage cor. East 25.10'
- 1998: Found $\frac{1}{2}$ "x18" iron in monument box and 6" below found $\frac{3}{4}$ "x12" iron 0.07' South & 0.06' East of surface iron. Noted Portage corner East 25.16'

11/19/98
R. E. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13: Southeast corner, Section 33, T. 2 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on November 19, 1998 and is accepted as the best available evidence of the position of the original corner. Found $\frac{1}{2}$ "x18" iron in monument box with $\frac{3}{4}$ "x12" iron below. Lower iron is believed to have been placed after sewer construction in 1961 to replace tile set by F. Hodgman in 1885 Remonumentation Survey. Placed 20" Harrison monument in monument box in place of iron.

1" Iron	in Monument Box	S. 54 ⁰ W.	44.60'
PK Nail in West Side	Power Pole	N. 38 ⁰ E.	80.73'
PK Nail in East Side	Power Pole	N. 20 ⁰ W.	64.48'
Nail/Tab in East Side	Power Pole (in conc. walk)	S. 50 ⁰ E.	55.56'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-18-98