

FEB 08 1999

LIBER 2 PAGE 438

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>11W</u>	<u>I-04</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 29 AM 11 26
Clerk - Register
Annell Johnson

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Oct. 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1827: United States Government Surveyors; set 1/4 post.
Lynn 8" S. 18° E. 8 lks.
Lynn 12" N. 24° W. 33 lks.

1885: F. Hodgman, County Surveyor; "Found old stake with stone and slag around it, in line with fence running East and 50 lks. from fence on East side of road. Set post with stone around," Elm 10" S. 19° E. 151 3/4 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1966: Wilkins & Wheaton Engr. Co.; found tile in center bound. No witnesses.
1998: Found 3" round tile with "x" on top in center bound in old Riverview Drive.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
11-19-1998
R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-04: East 1/4 post, Section 10, T. 2 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on November 11, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top as set by F. Hodgman, County Surveyor in 1885 Remonumentation survey in center bound. Placed remonumentation sleeve over tile.

Exist. Nail/Tab in South Side	Power Pole	S. 45° W.	36.02'
Exist. Nail/Tab in West Side	Power Pole	N. 20° E.	64.15'
PK Nail in West Side	Power Pole	S. 15° E.	86.05'
South Entrance	Post	N. 75° E.	34.85'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date 12-29-98