

7-2  
 SURVEY & REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 '95 JUN 6 AM 9 06  
 CLERK-REGISTER

For corners in Kalamazoo (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

Kalamazoo Township

1. Public Land Survey T 2 S R 11 W I-12  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on October 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1827: United States Government Survey; Set 1/4 Section Post.  
 Wh. Oak 10" South 40° East 19 Lks
  - 1885: F. Hodgman, County Surveyor; Found brick planted at intersection of fences. No witnesses. Set 2' earthen (post) with brick under and marked.  
 Wh. Oak 20" South 49½° West 60½ Lks  
 Wh. Oak 10" North 03½° East 18½ Lks

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994: Found 3" round tile with cross, 12" below surface.

LIBER 1 1306

RATIFIED  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP  
 1-19-95  
*R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 East 1/4 Post Section 34, T. 2 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on January 19, 1995. Found 3" round tile as called for in 1885 remonumentation survey by F. Hodgman, 12" below surface, and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed a remonumentation sleeve over tile.

PK Nail in South Side	22" Oak	North 84° West	19.88'
PK Nail in East Side	36" Oak	North 06° East	12.21' (1885 Witness)
PK Nail in North Side	18" Oak	South 72° East	12.95'
Southeast Corner of Brick House Foundation		North 20° East	66.28'

Signed by Robert E. Snell Date 6-02-95  
 Surveyor's Michigan License No. 9734