

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

APR 01 1996

'95 DEC 27 AM 10 38

For corners in

Kalamazoo
Kalamazoo (County) Twp.

Located In:

Corner Code #

- 1. Public Land Survey T 25 R 11 W K-2
w/4 post,
SEC. 1
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

James E. Boynton
REGISTER
LIBER 1 1422

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2	1			
3													
4	7		8		9		10		11	12			
5													
6	18		17		16		15		14	13			
7													
8	19		20		21		22		23	24			
9													
10	30		29		28		27		26	25			
11													
12	31		32		33		34		35	36			
13													

I, James E. Boynton, in a field survey on August 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827, original corner established by John Mullett, D.S.
1863, stake found by Stinson
1885, tile set in resurvey by F. Hodgeman
This corner is common to the plats of Maloney Plat, Plat of Parchmount and Brockmont Village No. 2.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile from the plats.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
10-19-95
R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Place standard sleeve over corner which was accepted as a perpetuation of the original corner by the Remonumentation Peer Group on 10-19-95.

- 8" Pine N. 37° W. 19.38'
- 4" Walnut N. 88° E. 14.95'
- 12" Maple S. 78° W. 25.24'
- Quadruple Cherry S. 06° E. 6.85'

Signed by James E. Boynton
Surveyor's Michigan License No. 29239

Date 12-17-95

