

**SURVEY &
REMONUMENTATION**

SEP 14 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Kalamazoo Township

Kalamazoo

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|-----|------|
| 1. Public Land Survey | T | 2S | R | 11W | K-08 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

0
Filed for Record in
KALAMAZOO COUNTY, MI
TIMOTHY A SNOW
On 05-08-1998 At 11:12:34 am.
LAND CORNER 9.00
OR Liber 2 Page 307 - 307

Instrument 0 OR Liber Page 2 307

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Jan. 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration: 1-15-1998

1827: United States Government Surveyors; set 1/4 post.

Beech 8" S. 07° W. 9 lks.
Beech 7" N. 31° E. 14 lks.

1885: F. Hodgman, County Surveyor; "Found fence post with stone beside, said by Healy (owner of adjacent land) to be in the place of the original corner post. Moved the fence post aside and put in place 3 ft. earthen post.

Maple 8" S. 68° W. 70½ lks.
Maple 8" S. 27° W. 55 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

1924: Glen C. Wheaton, County Surveyor; found tile.

1929: Same as above.

1947: Wilkins & Wheaton Engr. Co.; found tile at West 1/4 post Section 24.

1986: Wilkins & Wheaton Engr. Co.; replaced East 1/4 post Section 23, after removal of tile during sewer construction.

1997: Replaced East 1/4 post from previous survey information from 1986 job by Wilkins & Wheaton Engr. Co.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-08: East 1/4 post, Section 23, T. 2 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on January 15, 1998 and is accepted as a careful and faithful re-establishment of the position of the original corner. Re-established corner from information given in 1986 survey by Wilkins & Wheaton Engr. Co. Placed 20" Harrison monument in West shoulder of road.

Nail/Tab (Exist.) in South Side	Power Pole	N. 80° E.	22.96'
PK Nail in East Side	12" Ornamental Tree	S. 38° W.	31.80'
Notch in East Rim	Water Meter	West	6.64'
Nail in East Side	16" Elm	N. 35° W.	45.95'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 4-30-98