

APR 01 1996

COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 '95 DEC 8 AM 10 55

For corners in
KALAMAZOO
(County)

Located In:

Corner Code #

KALAMAZOO TWP.

1. Public Land Survey	T	<u>2S</u>	R	<u>11W</u>	<u>L7</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

James Young
CLERK-REGISTER

LIBER **1 1395**

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Gary D. Hahn, in a field survey on July 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 Quarter corner established by U.S. Deputy Surveyor Grange Risdon.
Accessories: W. Oak 6in N65W 19 lk W. Oak 6in N71E 17 lk.
- 1862 F. Stimson Co. Sur. "Iron stake mature ---? tree and stump standing."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered.
No iron stake recovered.
Found clay tile with "x" on top.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**
9-21-95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L7, North Quarter corner Section 24, T2S, R11W, Ratified by Kalamazoo County Remonumentation Peer Group on September 21, 1995. Tile location is accepted as a careful and faithful perpetuation of the position of the original corner. Set remonumentation survey marker cast iron sleeve over tile and witnessed:

- Set P.K. nail in 7" Sassafras S10°E 6.34'
- Set P.K. nail in 8" Sassafras N40°E 7.29'
- Set P.K. nail in 20" Sassafras N85°W 18.61'
- Set P.K. nail in 22" Hickory N10°E 22.68'

Signed by *Gary D. Hahn*

Date December 1, 1995

Surveyor's Michigan License No. 38116