

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo Located In: Corner Code #
(County)

Kalamazoo Section 1

1. Public Land Survey T 2 S R 11 W M-2
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 94 MAR 15 PM 1 37
 Clerk-Register
[Signature]

LBER 1 PG 1109
 Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on February 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						☼
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1825-U.S. Government Survey-set post
 Wh. Oak 24" South 42°-W 47 Lks (31.02')
 Y. Oak 16" North 59°-W 39 Lks (25.74')
- 1884-F. Hodgeman County Surevyor-found old stake North 42°-E, 47 lks from old U.S. Wh. Oak 24", set three-foot earthen post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" round tile with "X" on top, down about one foot.

[Signature]
RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 3-3-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-2 East 1/4 Post Section 1, T. 2 S., R. 11 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 3, 1994. Found 1"x1½' iron pipe over 3" round tile as called for in 1884 remonumentation by F.Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Placed remonumentation sleeve over tile and placed 1"x3' iron pipe over sleeve.
- PK Nail in SE side 17" Oak South 62°-W 15.91'
- PK Nail in E side 8" Elm North 18°-W 21.19'
- PK Nail in W side 10" Oak North 18°-E 18.45'
- Centerline of 4" steel fence post North 10°-W 1.31'

Signed by *[Signature]* Date 3-15-94
 Surveyor's Michigan License No. 9734