

**SURVEY &
REMONUMENTATION**

FEB 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2 PAGE 253

For corners in Kalamazoo Township

| | | |
|---------------------------------------|--------------------------|---------------|
| <u>Kalamazoo</u> (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T <u>2S</u> R <u>11W</u> | M-07 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 97 DEC 17 AM 9 30
 Clerk - Register
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Snell, in a field survey on Feb. 28, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors: Set post, corner to Sections 13 and 24.
 W. Oak 9" S. 21 1/2' W. 65 lks.
 W. Oak 12" N. 53 1/2' W. 57 lks.
- 1885: F. Hodgman, County Surveyor: Found iron stake set in previous survey from Comstock corner, set post and iron.
 Wh. Oak 6" N.W. 20 1/2 lks.
 Wh. Oak 20" S.E. 64 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1970: Kalamazoo County Road Commission: Sprinkle Road construction plans witness, iron with ring and cover, North 87.78' of Northwest corner Section 19, T. 2 S., R. 10 W. (witnesses gone except section corner).
- 1996: Found iron in monument in old road bed of Michigan Ave., down 3 ft. iron appeared to have brass cap on it. Note Harrison monument South 88.08' (Southwest corner Section 18 T. 2 S., R. 10 W.).

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 5-5-97**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-07: Southwest corner, Section 13, T. 2 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 15, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found iron pipe with 3/4" brass cap believed to have been set by M.D.O.T. surveyors in rebuilding of Route U.S. 12 A (abandoned in 1956). Placed 30" Harrison monument over pipe/brass cap.
- | | | | |
|------------------------|-------------------------|-----------|---------|
| Northeast corner | Concrete Block Building | N. 12° W. | 105.88' |
| Southeast corner | Concrete Block Building | N. 48° W. | 49.58' |
| P.K. nail in West side | Power Pole | N. 24° E. | 46.30' |
| Southwest corner | Steel Guard Rail Post | N. 68° E. | 14.60' |

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date 12-16-97