

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 '94 MAR 3 PM 3 50

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Kalamazoo Township		
1. Public Land Survey	T <u>2</u> S R <u>11</u> W	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Jamuel J. Young*  
 CLERK-REGISTER  
 1 PG 1102

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John G. Kester, in a field survey on October 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U.S. Government Deputy Surveyor John Mullett, 1825, set Post, Accessories: Elm 8 N21½W 20; Elm 15 N37W 23. Remonumentation by F. Hodgeman, 1885, Corner lost, bisected line 2-3, set Post (Solid Clay Tile with "X" on top), Accessories: Double Elm 8" N78E 64½ Lks. Kalamazoo County Road Commission Found Solid Clay Tile with "X" on top, 1956, Accessories: 28" Elm N80E 43.0'; 14" Maple S50E 45.60', Set construction witnesses, removed Tile during construction (cut 6'). W.D. Ingersoll set ½" Iron in 1957 from Road Commission construction witnesses. Kalamazoo County Road Commission found Ingersoll Iron in 1993, replaced with 30" Harrison Monument in Monument Box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner Post and Accessories not found.  
 Found ½" Iron in Monument Box established by Ingersoll from Road Commission construction witnesses of Tile set by F. Hodgeman during Remonumentation in 1885.

*J.E.S.*  
**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 1-20-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12, E½ Corner Section 36, T2S-R11W, Ratified by Kalamazoo County Remonumentation Program Peer Group on January 20, 1994. Found ½" Iron in Monument Box set by Ingersoll in 1957 from Kalamazoo County Road Commission construction witnesses of Solid Clay Tile with "X" on top called for in 1885 Remonumentation and is accepted as a careful and faithful perpetuation of the Original Corner position. Removed Monument Box, replaced ½" Iron with 30" Harrison Monument, placed Monument Box over Corner.

- Set ½" Rebar at Back of Curb West 31.95'
- Set ½" Rebar at Back of Curb East 32.10'
- S.W. Corner Inlet Casting S 50° E 40.56'
- Center of Storm Manhole S 10° W 27.61'

Signed by *John G. Kester* Date 2-28-94

Surveyor's Michigan License No. 16046  
 Kalamazoo County Road Commission