

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KALAMAZOO COUNTY
 (County)

Located In: _____ Corner Code \neq # _____

| | | | | | |
|---------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey | T | 25 | R | 12W | I-2 |
| | T | 25 | R | 12W | J-2 |
| 2. Property Controlling in Section | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, GARY C. BILOW, in a field survey on JULY 2, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-2: CORNER ESTABLISHED BY U.S. GOV'T DEPUTY SURVEYOR G. HARRISON IN 1830: ACCESSORIES - BEECH 13, S2BE, 10 & BEECH 10, S67N, 40. CORNER RECORDED UNDER ACT 74, P.A. 1970 BY A. McMACHEN (RLS#16935) IN 1972 IN LIBER 1 PAGE 181 AS "FOUND 3/4" IRON BAR FROM ACCESSORIES: TWIN 12" CHERRY, S75W, 21.06' - 5" CHERRY, S50E, 29.48' - 6" CHERRY, N30E, 72.21' & 30" WALNUT, N20E, 74.37'." THREE NEW ACCESSORIES ADDED: 16" OAK, N30W, 73.2' - 30" OAK, N9E, 96.6' - 12" CHERRY, N60E, 102.05'.

J-2: CORNER NOT ESTABLISHED BY GOVERNMENT SURVEY. CORNER ESTABLISHED BY COUNTY SURVEYOR HODGEMAN IN LATE 1800'S AS "SET IRON ACCESSORIES: WHITE OAK 12, WEST, 7 & WHITE OAK 16, S15E, 22." COUNTY SURVEYOR RECORDS AT FIRM OF WILKINS & WHEATON IN KALAMAZOO. CORNER RECORDED UNDER ACT 74, P.A. 1970 BY A. McMACHEN IN 1977 IN LIBER 1 PAGE 730 AS "SET IRON ROD FROM HODGEMAN'S WITNESSES - 48" OAK, WEST, 4.62' & 48" OAK, S15E, 14.52'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-2: FOUND 3/4" IRON BAR AND RECOVERED ONE ACCESSORY. ACCEPTED THIS CORNER AS THE BEST EVIDENCE OF THE ORIGINAL GLO CORNER.

J-2: FOUND 1/2" CAPPED (RLS#16935) IRON BAR AND ONE WITNESS - SECOND WITNESS IS NOW A DECAYED STUMP. ACCEPTED THIS CORNER AS THE CENTER 1/4 CORNER OF SECTION 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|--|---|
| I-2: FOUND 3/4" IRON BAR S50E 29.63', NAIL & MICHIGAN DEPARTMENT OF NATURAL RESOURCES TAG IN 12" WILD CHERRY S15W 11.40', NAIL & MDNR TAG IN FENCE POST N45W 60.73', SOUTHEAST CORNER BRICK HOUSE N38W 109.35', NAIL & MDNR TAG IN UTILITY POLE N15W 74.00', FOUND NAIL & TAG IN 42" OAK | J-2: FOUND CAPPED (RLS#16935) IRON BAR WEST 3.74', NAIL & MICHIGAN DEPARTMENT OF NATURAL RESOURCES TAG IN SE FACE 48" OAK S2SE 4.78', NAIL & MDNR TAG IN 6" WILD CHERRY EAST 7.03', NAIL & MDNR TAG IN 10" WILD CHERRY N26E 14.00', NAIL & MDNR TAG IN 10" WILD CHERRY |
|--|---|

Signed by Gary C. Bilow Date 5/22/91
 Surveyor's Michigan License No. 26453

