

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
KALAMAZOO COUNTY  
 (County)

Located In: \_\_\_\_\_ Corner Code ~~##~~

- |                                    |   |           |   |            |            |
|------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey              | T | <u>2S</u> | R | <u>12W</u> | <u>K-1</u> |
|                                    | T | <u>2S</u> | R | <u>12W</u> | <u>K-2</u> |
| 2. Property Controlling in Section | T | _____     | R | _____      | _____      |
|                                    | T | _____     | R | _____      | _____      |
| 3. Miscellaneous Property in Sec.  | S | _____     | T | _____      | _____      |
|                                    | S | _____     | T | _____      | _____      |

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GARY C. BILOW, in a field survey on JULY 2, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-1:** CORNER ESTABLISHED BY U.S. GOV'T DEPUTY SURVEYOR G. HARRISON IN 1830; ACCESSORIES - BEECH 6,S59E,53 & BEECH 6,S25W,27. COUNTY SURVEYOR HODGEMAN RECORDED THREE WITNESSES (SUGAR 30,S50W,14 - ASH 8,S21E,30 - WALNUT 6,S35E,37) BUT NO MENTION OF WHAT FOUND OR SET IN COUNTY SURVEYOR RECORDS (FIRM OF WILKINS & WHEATON HAVE COUNTY SURVEYOR RECORDS) IN LATE 1800'S. WILKINS & WHEATON RECORDED IN SAME RECORDS "PLACED 1/2" IRON FROM WITNESS TREE - NEW ACCESSORY: EAST 232' A FENCE GOING NORTH. FROM RECORDS OF GOVE & ASSOCIATES DATED 1962 - 1/2" IRON ROD IN MONUMENT BOX - ACCESSORIES: FENCE POST,N65W,52.91'-FENCE POST,57W,32.80'-FENCE POST,S45E,45.46'-48" ELM,S65E,65.25'.
- K-2:** CORNER ESTABLISHED BY U.S. GOV'T DEPUTY SURVEYOR G. HARRISON IN 1830; ACCESSORIES - BEECH 12,N24W,10 & BEECH 15,S87E,39. COUNTY SURVEYOR HODGEMAN RECORDED IN LATE 1800'S "STONE IN CENTER OF RAILROAD-ACCESSORIES: RED OAK 18,N7W,56-WHITE OAK 9,S71E,77-STONE,NORTH,85." FROM GOVE ASSOCIATES RECORDS DATED 1957 "SET T-IRON FROM 2 WITNESS POINTS FROM WILKINS."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- K-1:** FOUND 5/8" IRON BAR IN MONUMENT BOX AND ACCEPTED THIS CORNER AS THE BEST EVIDENCE OF THE ORIGINAL GLO CORNER.
- K-2:** FOUND 1/2" IRON BAR IN MONUMENT BOX AND ACCEPTED THIS CORNER AS THE BEST EVIDENCE OF THE ORIGINAL GLO CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |  |
|--|--|
| <b>K-1:</b> FOUND 5/8" IRON BAR IN MONUMENT BOX<br>N50W 36.37', NAIL & DEPARTMENT OF NATURAL RESOURCES TAG IN 9" ELM<br>N64E 38.83', NAIL & MDNR TAG IN WEST SIDE GUARD RAIL POST<br>S50E 52.50', NAIL & MDNR TAG IN NORTH SIDE GUARD RAIL POST<br>S45W 61.21', NAIL & MDNR TAG IN 12" ELM | <b>K-2:</b> FOUND 1/2" IRON BAR IN MONUMENT BOX<br>S45W 24.44', NAIL & MDNR TAG IN GUARD RAIL POST<br>S32W 57.11', NAIL & MDNR TAG IN UTILITY POLE<br>N37W 72.03', NAIL & MDNR TAG IN 5" POPLAR<br>S30E 38.35', NAIL & MDNR TAG IN GUARD RAIL POST |
|--|--|

Signed by Gary C. Bilow Date 5/22/91  
 Surveyor's Michigan License No. 26453

