

SURVEY & REMONUMENTATION

7-3- AUG 22 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 AUG 1 PM 4 08

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
<u>Oshtemo Township</u>		
1. Public Land Survey	T <u>2 S</u> R <u>12 W</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. [Signature]

CLERK - REGISTER

LIBER

1 ■ 1314

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on June 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829: United States Government Survey; Enter West boundry 29 Lks South of Post. Set Post at Intersection of Corners 19 and 30.

Bl. Oak 10" North 52 1/2° East 150 Lks
Bl. Oak 12" South 66 1/2° East 184 Lks

1871: Ed Strong, County Surveyor; Section Corner stone from former survey. One witness still standing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found Old Railroad Spike in bituminous surfaced road with a 10" x 8" stone, 19" below surface of road.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-20-95 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 Northeast Corner Section 30, T. 2 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 20, 1995 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found Railroad Spike over 10" x 8" stone, 19" below surface of road. Placed 16" of 20" Harrison monument over stone and in former position of Railroad Spike with a monument box over.

Exist. Nail/Tab in West Side 46" Maple North 20° East 89.70'
Exist. Nail/Tab in South Side 6" Elm North 60° East 65.74'
Exist. Nail/Tab in South Side 36" Maple South 30° East 46.77'
Exist. Nail/Tab in South Side 8" Sassafras North 40° West 34.88'
Exist. 1/2" Iron Rod North 19.08'

Signed by *Robert E. Snell* Date 7-27-95

Surveyor's Michigan License No. 9734