

SURVEY & REMONUMENTATION

2 - AUG 22 1995

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'95 AUG 1 PM 4 08

For corners in COMMISSION

| | | |
|---------------------------------------|----------------------------|---------------|
| Kalamazoo <small>(County)</small> | Located In: | Corner Code # |
| Oshtemo Township | | |
| 1. Public Land Survey | T <u>2</u> S R <u>12</u> W | <u>A-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

James J. Young
CLERK-REGISTER

LIBER **1 1313**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 13 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Robert E. Snell, in a field survey on June 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
This Corner Not Set by original government surveyors.

1982; Ed Strong, County Surveyor; West 1/4 Stone
Y. Oak 10" Southeast 68 Lks
1900: Ed Strong, County Surveyor; West 1/4 found good

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found stone just below bituminous surface of road. No markings on stone.
A bolt was found on South side of stone.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-20-95
R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 West 1/4 Post Section 30, T. 2 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 20, 1995. This Corner was not placed by original government surveyors. Found stone as mentioned by Ed Strong in surveys in 1892 and 1900 and is accepted as the best available evidence of the position of the corner as established. Lowered stone and placed a 20" Harrison monument and existing monument box over stone.

| | | | |
|--------|----------------------------------|----------------|---------|
| Exist. | Cap/Iron (10935) | South 88° East | 32.97' |
| Exist. | Nail/Tab in West Side Triple Oak | South 10° East | 128.52' |
| Exist. | 1/2" Iron Rod | North 78° West | 32.88' |
| Exist. | Harrison Monument | North | 11.14' |

Signed by *Robert E. Snell* Date 7-28-95
Surveyor's Michigan License No. 9734