

SURVEY & REMONUMENTATION

FEB 26 1998

LIBER PAGE 266

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 DEC 23 PM 12 56
Clerk - Register

<u>Kalamazoo</u>	Located In:	Corner Code#
(County)		
<u>Oshtemo Township</u>		
1. Public Land Survey	T <u>2S</u> R <u>12W</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gary D. Hahn, in a field survey on April 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8/21/97

A. Description of original monument and accessories and/or subsequent restoration:

1830 - NW corner established by U.S. Deputy Surveyor Geo. W. Harrison.
Witness Ties: W. Oak 5 N 8 deg. E 70 L
W. Oak 5 S 55 deg. E 264 L

1900 - E. Strong "Set stone (reference only) near E. line of road"



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found RR spike in pavement. Removed spike and dug a 4' x 4' hole. Found 4" x 7" stone two feet below road surface in sandy soil. No other stones or accessory evidence found. Stone was 0.78 feet north and 0.81 feet east of spike. Probed additional 4 to 5 feet in sand. No other evidence found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11, Northwest Corner Section 31, Town 2 South, Range 12 West, ratified by Kalamazoo County Remonumentation Peer Group on August 21, 1997. Position of 4" x 7" stone is accepted as the best available evidence of the original position of the closing corner. Set a 20" Harrison Monument on the east line of Alma Township, Van Buren County at the government jog distance of 3.30 feet south of the previously ratified position of the NE corner of Section 36, said Alma Twp.

Witness ties: Set 1/2 inch rebar at back of curb S 45 deg. W 46.10 feet.
Set 1/2 inch rebar at back of curb S 45 deg. E 40.03 feet.
Set 1/2 inch rebar at back of curb N 45 deg. E 44.59 feet.
Set PK nail in 26" Oak N 45 deg. W 57.53 feet.

Signed by [Signature]
Surveyor's Michigan License No. 38116

Date 12/19/97