

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 DEC 8 AM 10 55

Form with fields: For corners in KALAMAZOO (County), Located In: OSHTEMO TWP., Corner Code # B11, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Section, 4. Lot No., 5. Private Claims

James Young
CLERK-REGISTER

LIBER 1 1401

Register of Deeds Stamp & File Number

I, GARY D. HAHN, in a field survey on MAY 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 Quarter post established by U.S. Deputy Surveyor Geo. W. Harrison
Accessories: W. Oak 6 N17°E 221 W. Oak 4 S89°W 121
1900 E. Strong Co. Sur. "Found good"
1935 KCRC notes: (W) Fd. stone & stake below. Placed iron below and on top of stone.
Maple B.T. stump ok Line cement post 35' N. 6" Y.O. N20°W 37.0'
Date? KCRC notes: 3/4" iron (Gove) 30" T. Oak N60°E 35.07' 18" Sass. S25°E 73.32'
12" Oak S45°W 48.94' 24" Oak N20°W 37.16'
1974 John Corbit RLS 3101 LCRC Liber 1, Page 441 Found 3/4" iron. 14" Sass. S30°E 73.21'
30" T. Oak N55°E 36.38' 26" Oak N25°W 37.42'
1988 Thomas Chettleburgh LCRC Liber 1, Page 884 Found 3/4" iron bar. See LCRC for witness ties.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered.
Found 7/8" rod under asphalt road.
Found 5/8" rod 6" deep along side 7/8" rod.
Found pointed rock with small stones around below irons. (Directly below irons)

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-15-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B11, South quarter corner Section 30, T2S, R12W, Ratified by Kalamazoo County Remonumentation Peer Group on June 15, 1995. The location of the stone is accepted as a careful and faithful perpetuation of the position of the original corner. Removed irons and set a 20" Harrison Monument directly over pointed stone. Set monument in mon. box.

- Found nail with tab in 20" Oak N37°E 27.37'
Set P.K. nail in 15" Oak S50°W 48.87'
Fnd. nail with tab in 32" Oak N25°W 37.58'
Set P.K. nail in 15" Oak S75°E 86.00'

Signed by Gary D. Hahn
Surveyor's Michigan License No. 38116

Date 9-1-95

