

SURVEY & REMONUMENTATION

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code #
(County)		
Oshtemo Township		
1. Public Land Survey	T <u>2S</u> R <u>12W</u>	<u>C-10</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 97 AUG 25 AM 11 57
 CLERK - REGISTER
Janice Johnson

LIBER 2 PAGE 192

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Thomas W. Chettleburgh, in a field survey on July 30, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E. Strong, 1892, Found corner
 McMachen, Found 3/4" iron bar adjacent to very old stump
 Nail/tag 18" Oak N10°E 32.92'
 Nail/tag 24" Oak S26°W 36.67'
 Nail/tag 12" Ash West 15.91'
 Old fence corner 2' SW, old fences running South & West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" old iron axle, checks above witnesses
 The found 3/4" old iron axle ratified by the Kalamazoo County Remonumentation Program Peer Group on July 16, 1997 and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 3/4" old iron axle with 30" Harrison Monument.
 Spike W side 17" Maple N04°E 32.92'
 Spike N side 12" Wild Cherry N89°E 15.12'
 Spike NE side 13" Beech S52°E 60.48'
 Spike SE side 26" Oak S27°W 36.65'
 Spike N side 13" Ash S86°W 15.92'

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 7-16-1997



Signed by Thomas W. Chettleburgh
 Surveyor's Michigan License No. 16036

Date July 31, 1997