

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 95 NOV 16 PM 3 26

For corners in Oshtemo Township  
Kalamazoo  
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>2S.</u>	R	<u>12W.</u>	<u>D-5</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

*James J. Jones*  
 CLERK-REGISTER

LIBER **1 1370**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 6. IWM JOB No. 27236

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5			●									
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Allen H. McMachen, in a field survey on May 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 - G. Harrison, D.S., Set 1/4 Section post  
 Wh. Oak 8" S. 12° W. 19 lks.  
 Wh. Oak 6" N. 31° E. 10 lks.

1907 - Ed Strong, C.S.

Bisected South line, set marked stone and brick. This may not be where the U.S. 1/4 was. A further survey is advisable from S. 1/4 of 17 by doubling the 1/4 line over the Center 1/4 of 17, the present stone is about 1 rod East of the road as now used. But I dug a trench across the road E. & W. 15' and found nothing. All bearings gone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron in Mon. box 16.55' East of 3/4" pipe in construction centerline 3rd Street. Removed 3/4" iron and box and found Pointed stone with hole in top 2.5' below grade, directly under 3/4" iron. Found stone is surrounded by smaller stones. Ingersoll, Watson & McMachen, Inc. measured from pointed stone to Southwest corner @ 2634.00' and Pointed stone to Southeast corner @ 2632.00'.

RATIFIED  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP  
 6-15-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Pointed stone is accepted as a careful and faithful re-establishment of the original corner. Removed 3/4" iron and placed Harrison Monument over found stone and Mon. box, Accessories:

- Nail & Tab in 30" Maple N. 30° W., 76.59'
- Nail & Tab in 12" Triple Box Elder N. 55° E. 65.68'
- Nail & Tab in 8" Cherry S. 60° W. 58.58'
- Nail & Tab in 10" Elm S. 40° W. 76.98'



Signed by Allen H. McMachen  
 Surveyor's Michigan License No. 16935

Date 11/16/95