

1
2
SURVEY &
REMONUMENTATION

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo Located In: Corner Code #
(County)
Oshtemo Township
1. Public Land Survey T 2S R 12W D-10
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'97 AUG 25 AM 11 57
CLERK - REGISTER
Amelia Johnson
LIBER 2 PAGE 195
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas W. Chettleburgh, in a field survey on July 30, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		●		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E. Strong, 1898, Found old stone correct set stake and set stone over old stone
- J. Corbit, 1979, Used corner

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3-21-1996
R. G. S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found pointed flint stone below ring of stones
- Found stone 3.09' N. of E-W 1/4 line
- Found pointed flint stone ratified by the Kalamazoo County Remonumentation Program Peer Group on March 22, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. This corner not set by Original Government Surveyors.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replaced pointed flint stone with 30" Harrison Monument
- Spike SE side 16" Oak N32°E 26.48'
- Spike SW side 32" Oak S65°E 37.60'
- Spike W side 12" Oak S7°W 37.33'
- Spike SE side 6" Oak S73°W 16.83'
- Spike SW side 7" Oak N33°W 7.66'



Signed by *Thomas W. Chettleburgh*
Surveyor's Michigan License No. 16036

Date July 31, 1997