

SURVEY & REMONUMENTATION

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code #
(County)		
Oshtemo Township		
1. Public Land Survey	T <u>2S</u> R <u>12W</u>	<u>D-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 97 AUG 25 AM 11 57
 Clerk - REGISTER

LIBER 2 PAGE 189

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Thomas W. Chettleburgh, in a field survey on July 30, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- F. Stimson, 1863, Found stake.
- E. Strong, 1898, Found stake from 1863 witnesses
- McMachen, 1969, Found pencil iron, set 1/2" iron & monument box
- Gove, 1972, Found 1/2" iron in monument box
- 18" Oak S50°W 38.49' 10" Hickory S15°E 27.25'
- 12" Oak N10°W 33.33' 18" Oak N30°E 51.51'
- J. Corbit, 1979, Found 1/2" iron in monument box

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 7-16-1997
R.E.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron bar in monument box, checks witnesses above
 The found 1/2" iron bar was ratified by the Kalamazoo County Remonumentation Program Peer Group on July 16, 1997 and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replaced 1/2" iron bar with 20" Harrison Monument inside monument box
- Spike SE side 23" Oak N37°E 51.49'
- Spike SW side 25" Oak S66°E 75.35'
- Spike E side 16" Hickory S00°E 53.03'
- Spike NW side 24" Hickory S25°W 23.35'
- Spike NE side 18" Oak N16°W 33.24'



Signed by Thomas W. Chettleburgh
 Surveyor's Michigan License No. 16036

Date July 31, 1997