

APR 01 1996

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

96 JAN 23 PM 3 50

For corners in
Kalamazoo
(County)

Located in:

Corner Code #

Oshemo Twp.

- | | | |
|--------------------------------------|------------------------------|-------------|
| 1. Public Land Survey | T <u>2</u> S. R <u>12</u> W. | <u>D-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

James D. Young
CLERK-REGISTER

LIBER **1 1438**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Decmeber 21,, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original Government Surveyors.

1879: F. Hodgman, County Surveyor; center of Section set by some former survey. Found the stake from two witnesses.

1890: E. Strong, County Surveyor; found all right, set stone.

1904: Michigan Central Railroad, A.L. Sarvey; monument boulder, with drilled center.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found stone with drill hole.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-14-95
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-12: Center of Section 32, T. 2 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on December 14, 1995 and is accepted as the best available evidence of the position of the corner. This position not established by original Government Surveyors. Found drilled stone as called for by E. Strong in 1890 Survey. Removed stone and placed a 30" Harrison Monument in its place.

60 d Nail in North Side	8" Hickory	N. 45° E.	15.90'
60 d Nail in North Side	24" Cherry	East	13.21'
60 d Nail in South Side	14" Oak	N. 65° W.	44.58'
60 d Nail in East Side	20" Oak	South	38.90'

Signed by *Robert E. Snell* Date 1-18-96

Surveyor's Michigan License No. 9734