

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code #
(County)		
<u>Oshtemo Township</u>		
1. Public Land Survey	T <u>2S</u> R <u>12W</u>	<u>D-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'97 AUG 25 AM 11 57
Clerk - Register
Annexed

LIBER 2 PAGE 190

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Thomas W. Chettleburgh, in a field survey on May 27, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Hodgeman, 1879, Found stake, set new stake with stone
McMachen, 1986, Set iron bar at mid-point and on line between Section corners (E-13 & C-13).
Iron bar fell in center of ring of stones at edge of pond.
20" Oak N20°W 27.65', 4" Hickory N45°W 12.63'
4" Oak N89°W 27.14', Iron bar S35°W 15.40'
Gregory Smith, 1986, Found iron bar set by McMachen, recorded L.C.R.C. Liber 1, Pg 936

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron bar in center of ring of stones as set by McMachen - checked above witnesses.
The iron bar was ratified by the Kalamazoo County Remonumentation Program Peer Group on July 16, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron bar with 30" Harrison Monument

Spike in	E side	12" Maple	N11°E	41.66'
Spike in	W side	36" Oak	S13°W	34.80'
Spike in	SE side	33" Oak	S33°W	16.30'
Iron bar	(north side)	33" Oak	S37°W	15.40'
Spike in	N side	28" Oak	S85°W	65.06'
Spike in	SW side	16" Oak	N66°W	67.77'
Spike in	NE side	6" Hickory	N45°W	28.44'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-16-1997



Signed by Thomas W. Chettleburgh
Surveyor's Michigan License No. 16036

Date August 18, 1997