

SURVEY & REMONUMENTATION

7
2
SEP 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Oshtemo Twp.

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo

Located In:

Corner Code #

1. Public Land Survey	T	<u>2S</u>	R	<u>12W.</u>	<u>E-2</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 MAR 26 PM 3 37
Clerk - Registrar
[Signature]

LIBER 2 PAGE 291

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on January 28, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 - George W. Harrison, D.S., Set 1/4 Section post, Wh. Oak 6" N. 69° E. 36 lks., Wh. Oak 5" N. 34 1/2° W. 77 lks..
- 1882 - Ed Strong, "Left stake at West quarter but did not find complete evidence nearer than 2'.
- 1897 - Ed Strong, C.S., "Set stone from U.S. good."
- 1904 - Ed Strong, C.S., "Good U.S.-Stone of former Survey."
- 1972 - Ingersoll, Watson & McMachen, Inc., "Found stone with drill hole", 16" Oak North 25.26', 14" Oak East 16.36', 30" Oak S. 60° E. 30.78', 14" Oak N. 45° W. 14.88'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone with drill hole per (2) 1972 witnesses. Found drilled stone above grade surrounded with smaller stones.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
2-19-1998
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found stone with drill hole is accepted as a careful and faithful perpetuation of the position of the original corner. Removed drilled stone and replaced with a 30" Harrison Monument at drill hole location and piled stones that surrounded Section corner stone back around Harrison Monument. Corner is in downed fence line East & West, Accessories:

- Nail in East side 16" Oak North 24.90'
- Nail in North side 14" Oak East 16.15'
- Nail in N.E. side 36" Oak S. 60° E. 30.75'
- Nail in North side 16" Oak West 54.50'



Signed by *[Signature]*
Surveyor's Michigan License No. 16935

Date 2/24/98