

SURVEY & REMONUMENTATION

1
2
SEP 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>2S</u>	R	<u>12W.</u>	<u>E-5</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER
CLERK - REGISTER
2 PAGE 293
93 MAR 26 PM 3 27
STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Allen H. McMachen, in a field survey on January 22, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5		4	3		2		1			
3												
4	7	8		9	10		11		12			
5												
6	18	17		16	15		14		13			
7												
8	19	20		21	22		23		24			
9												
10	30	29		28	27		26		25			
11												
12	31	32		33	34		35		36			
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 - George W. Harrison, D.S., Set post cor. to Secs. 8, 9, 16 & 17, Wh. Oak 12" S. 62½° W. 80 lks., Wh. Oak 3" N. 54½° E. 43 lks..
- 1907 - Ed Strong, C.S., "Found good hole, set marked stone, Hickory N. 01° W. 32 lks., Y. Oak 10" S. 01° E. 8 lks..
- 1912 - Ed Strong, C.S., "Found stone & glass", U.S. Hickory stump, Apple S. 45° W. 65 lks..

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone near intersection of tree lines and possibly matching (1) 1907 witness to Oak. Stone meas. 1' X 1.5' X 2.3'.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
2-19-1998 *R. E. S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found pointed stone is accepted as the best available evidence of the position of the original corner. Stone too large to remove from hole. Enlarged hole to West and rolled stone on its side. Placed 30" Harrison Monument at location of point of stone, Accessories:

- Nail in West side 20" Oak North 17.25'
- Nail in North side 12" Sassafras S. 65° E. 11.00'
- Nail in East side 28" Oak S. 15° W. 6.35'
- Nail in Northwesterly side 14" Cherry S. 70° W. 13.07'



Signed by Allen H. McMachen

Date 2/24/98

Surveyor's Michigan License No. 16935