

SURVEY & REMONUMENTATION

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 AUG 25 AM 11 57
Clerk - Register
Annellee Brown

For corners in

| | | |
|------------------------------------|--------------------------|---------------|
| <u>Kalamazoo</u> | Located In: | Corner Code # |
| (County) | | |
| Oshemo Township | | |
| 1. Public Land Survey | T <u>2S</u> R <u>12W</u> | <u>E-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

LIBER 2 PAGE 193

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Thomas W. Chettleburgh, in a field survey on July 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Stimson, 1865, Set stake, stone & old iron
- McMache, 1971, Set iron bar by running E-W 1/4 line, Section 28
Found iron bar 2.1' South
- John Hunt, 1992, Found iron bar set by McMachen and recorded LCRC
Liber 1, Page 979, also found iron bar 2.1" Southerly

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-16-1997
R.L.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron bar as set by McMachen and recorded by John Hunt
Also found iron bar 2.1' South and 0.2' East
Dug under both irons - found nothing
The found iron bar as set by McMachen was ratified by the Kalamazoo County Remonumentation Program Peer Group on July 16, 1997 and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | | | |
|---|---------|------------|-------|--------|
| Replaced iron bar with 20" Harrison Monument and monument box | | | | |
| Spike | NW side | Light pole | N30°E | 62.00' |
| Spike | SW side | 18" Oak | S34°E | 88.67' |
| Iron Bar | | | S05°E | 2.1' |
| Spike | SE side | 31" Oak | S41°W | 49.78' |
| Spike | N side | Power Pole | N87°W | 59.72' |



Signed by *Thomas W. Chettleburgh*
Surveyor's Michigan License No. 16036

Date July 28, 1997