

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo Located In: Corner Code #  
(County)

Oshtemo Township  
1. Public Land Survey T 2S R 12W E-11  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
97 AUG 25 AM 11 57  
Clerk - Register  
*Jennifer Brown*

LIBER 2 PAGE 194

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas W. Chettleburgh, in a field survey on July 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

- Stimson, 1865, Set Burr Oak stake & stones
- E. Strong, 1890, Found corner
- McMachen, 1969, 1/2" iron in monument box  
24" Maple N75°E 32.9', Power Pole N15°W 75.6', 16" Oak S50°W 52.6'
- J. Corbit, 1979, Found nail, over stone  
33" Maple N71°E 33.18', Power Pole N22°W 75.96', 24" Oak S54°W 53.15'

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
7-16-1997  
*T.W.C.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found P.K. nail in road surface over ring of stones 24" deep.  
Found iron bar 33.00' East  
P.K. nail checks J. Corbit, 1979, witnesses  
The found P.K. nail over ring of stones was ratified by the Kalamazoo County Remonumentation Program Peer Group on July 16, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replaced P.K. nail with 20" Harrison Monument and monument box
- Spike N side Light pole N86°E 26.87'
  - Spike SW side 33" Maple S19°E 77.20'
  - Spike SE side Power Pole S14°W 123.83'
  - Spike SE side 24" Walnut S20°W 88.98'
  - Spike NE side Power Pole N12°W 75.95'



Signed by *Thomas W. Chettleburgh*  
Surveyor's Michigan License No. 16036

Date July 28, 1997