

SURVEY & REMONUMENTATION

1
2
SEP 14 1998

SECTION LAND CORNER RECORDATION CERTIFICATE
Oshtemo Twp. Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>2S</u>	R	<u>12W.</u>	<u>F-5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

LIBER
CLERK - REGISTER
2 PAGE 294
'98 MAR 26 PM 3 37
STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on January 22, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 - George W. Harrison, D.S., Set 1/4 Section post, Bl. Oak 3" N. 80 1/2° E. 149 lks., Wh. Oak 4" North 194 lks..
- 1873 - Ed Strong, C.S., Y. Oak 5" S. 50° E. 2 lks.. Found U.S..
- 1908 - Ed Strong, C.S., "Found marked stone at bearing tree."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone at intersection of tree rows North, South, East & West. Stone meas. 1' X 1' X 1.5'.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
2-19-1998
R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Pointed Stone is accepted as a careful and faithful perpetuation of the position of the original corner. Removed stone and replaced with 30" Harrison Monument at location of point of stone, Accessories:

- Nail in West side 5" Hickory N. 10° E. 5.90'
- Nail in North side 12" Hickory S. 60° E. 4.85'
- Nail in Northwesterly side 10" Hickory S. 60° W. 11.68'
- Nail in North side 10" Hickory West 16.30'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 2/24/98