

1
2 APR 01 1996

LIBER 1 1442

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Kalamazoo
(County)
Oshtemo Twp.

Located In:

Corner Code #

1. Public Land Survey	T	2 S.	R 12 W.	F-12
	T		R	
	T		R	
	T		R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Section	S	T	R	
	S	T	R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
96 JUN 29 PM 2 15
REGISTER-REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert E. Snell, in a field survey on June 13, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original Government Surveyors.

1866: F. Stimson, County Surveyor; center of Section established by bisecting 1/4 lines. Planted stake from which

Hickory 10" South 163 lks.
Hickory 16" N. 32° E. 2.25 lks.

1892 & 1911: E. Strong, County Surveyor; found drilled stone 9" below.

Hickory 18" N. 32° E. 2.22 lks.
Hickory 14" S. 45 1/4° E. 2.14 lks. Fence West 10.00 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1992: Found drilled stone 0.76' West of calculated intersection.

Stone is 5" x 10" tall, flat on top.
Center line double 10" dead tree 3.9'
Center line 6" Pine S. 20° W. 1.7'
Center line 10" Maple N. 35° W. 8.7'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-14-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-12: Center of Section 33, T. 2 S., R. 12 W., ratified by Kalamazoo County Remonumentation Program Peer Group on December 14, 1995 and is accepted as best available evidence of the position of the corner. This position not established by original Government Surveyors. Found stone as set by F. Stimson in 1866 survey and found by E. Strong in 1892 and 1911. Removed stone and placed 30" Harrison Monument in its place.

PK Nail in West side 13" Pine S. 30° W. 25.87'
PK Nail in South side 11" Sassafras N. 68° W. 40.72'
PK Nail in West side 14" Pine N. 02° W. 19.64'
PK Nail in North side Multi-Maple N. 80° E. 17.74'

Signed by

Robert E. Snell

Date

1-26-96

Surveyor's Michigan License No.

9734