

SURVEY & REMONUMENTATION

APR 27 1995

LIBER 1 PG 1152

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
94 JUL 6 AM 11 52
Janet [Signature]
CLERK - REGISTER

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
<u>Oshtemo Township</u>		
1. Public Land Survey	T <u>2S</u> R <u>12W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Thomas W. Chettleburgh, in a field survey on March 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Corner Post set by U.S. Government Deputy Surveyor William Brookfield, 1827.
 Accessories: Hickory 10 N33 1/2E 1.25, W Oak 9 N37 1/4W 1.98.
 Ed Strong, 1913, Found stone.
 Wilkins & Wheaton, Large iron pin East side of South end road.
 D. Erickson, 1992, Found 1" iron pin at East side of South end road, recorded LCRC Liber 1, Page 974
 Accessories: 10" Oak S53W 23.40', 36" Oak S81°E 17.33'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Original Corner Post & Accessories not recovered.
 Stone by Ed Strong not recovered.
 Found 1" iron pin as described and recorded by D. Erickson, the 1" iron pin was accepted as a careful and faithful perpetuation of the position of the original corner and was ratified by the Kalamazoo County Remonumentation Program Peer Group on April 21, 1994.
 Replaced 1" iron pin with 30" Harrison Monument.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 4-21-94 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 30" Harrison Monument
- 4" Diameter Harrison Monument (N 1/4 Cor. Sec. 4, T3S, R12W) S87°E 104.94'
- Spike NW side 6" Hickory S35°W 8.35'
- Spike N side 9" Hickory S85°W 11.33'
- Spike NW side 9" Oak N29°E 21.20'
- Spike S side 30" Oak S87°E 17.28'



Signed by Thomas W. Chettleburgh Date July 5, 1994
 Surveyor's Michigan License No. 16036