

# SURVEY & REMONUMENTATION

APR 27 1995

LIBER

1 PG 1153

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

CLERK - REGISTER

*Thomas W. Chettleburgh*

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
94 JUL 6 AM 11 52

For corners in

<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #
<u>Oshtemo Township</u>		
1. Public Land Survey	T <u>2S</u> R <u>12W</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Thomas W. Chettleburgh, in a field survey on January 31, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- Corner Post set by U.S. Government Deputy Surveyor William Brookfield, 1827.
- Accessories: Y Oak 18 N86 1/4W 19 links, Y Oak 18 N56 1/4E 1.21.
- Ed Strong, 1913, Stone.
- Kalamazoo County Witness Sheet stone with "X" in shoulder of road.
- Gove, 1970, Stone with "X" in shoulder of road.
- R. Snell, 1991, Set P.K. nail in road. Recorded LCRC Liber 1, Page 945 & LCRC Liber 1, Page 948
- Accessories: 8" Apple NW 57.04, USGS Bench mark SW 28.40'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Original Corner Post & Accessories not recovered.
- Found P.K. nail as described and recorded by R. Snell.
- Found stone with "X" 1.75' deep & 0.21' South of P.K. nail & in west shoulder of N-S road.
- The stone with "X" was accepted as a careful and faithful perpetuation of the position of the original corner and was ratified by the Kalamazoo County Remonumentation Program Peer Group on March 3, 1994.
- Set 20" Harrison Monument and Monument box directly over the stone with "X".

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
3-3-94 *R.S.F.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 20" Harrison Monument in monument box.
- 4" Diameter Harrison Monument (NE Cor. Sec. 4, T3S, R12W) S87°E 125.40'
- USGS bench mark (Bronze disc in concrete post) S80°W 28.35'
- Spike SW side 16" Maple N71°W 23.31'
- Spike E side 40" Maple N5°W 142.07'
- Spike W side Tw 21" Oak N16°E 136.25'
- Centerline N-S Road East 10.5'



Signed by *Thomas W. Chettleburgh* Date July 5, 1994

Surveyor's Michigan License No. 16036